

ROOM NUMBER	ROOM NAME	FLOORS			WALLS					CEILING			MISCELLANEOUS		ROOM NUMBER	FLOORS & BASES		WALLS		CEILING	
		FLOORING	BASE	REMARKS	NORTH	EAST	SOUTH	WEST	REMARKS	CEILING HEIGHT	CEILING	REMARKS	CABINETS	REMARKS		1		A		1	
101	WAITING ROOM	1	5		-	A	A	A	FURRED WALL AT EXT. WALL	-	3				101	1	SEALED & POLISHED CONCRETE	A	5/8" SHEETROCK (TAPE, TEXTURE & PAINT)	1	SUSPENDED CEILING - DONN DX 15/16" 2'x4' T-BAR GRID W/ ARMSTRONG CORTEGA MINIBOARD LAY-IN PANELS (OR EQUAL) COLOR: WHITE. INSTALL BOTTOM OF GRID PER SCHEDULE - PROVIDE SEISMIC BRACES PER DETAILS
102	KIDS	1	5	AREA RUG BY OWNER	A	A	-	A	FURRED WALL AT EXT. WALL	-	3				102	2	CARPET	B	CERAMIC TILE WAINSCOT OVER WATER-RESISTANT SHEETROCK TO 12" A.F.F. WITH PAINTED SHEETROCK ABOVE	2	5/8" SHEETROCK
103	RECEPTION	2	5		A	A	A	-		-	3				103	3	CARPET TILES	C	5/8" PLYWOOD - PAINTED	3	NO CEILING. EXPOSED TO STRUCTURE ABOVE
104	MAIL ROOM	1	5		A	A	A	A		-	3				104			D	(E) FINISH TO REMAIN - PAINT	4	(E) CEILING TO REMAIN UNCHANGED
105	MAIL & FILING	2	5		A	-	A	A		-	3				105					5	FACTORY FINISH
106	[NOT USED]														106	4	CERAMIC TILE	E	(E) FINISH TO REMAIN UNCHANGED		
107	FINANCE	2	5		A	A	A	A	FURRED WALL AT EXT. WALL	10'-0"	1				107	5	RUBBER BASE	F	FACTORY FINISH		
108	HALLWAY	1	5		A	A	A	A		-	3				108						
109	OFFICE	2	5		A	A	A	A	FURRED WALL AT EXT. WALL	10'-0"	1				109						
110	OFFICE	2	5		A	A	A	A	FURRED WALL AT EXT. WALL	10'-0"	1				110	6	COVED TILE BASE				
111	OFFICE	2	5		A	A	A	A	FURRED WALL AT EXT. WALL	10'-0"	1				111	7	(E) FLOORING TO REMAIN UNCHANGED				
112	OFFICE	2	5		A	A	A	A	FURRED WALL AT EXT. WALL	10'-0"	1				112	8	STATIC DISSIPATIVE FLOORING				
113	OFFICE	2	5		A	A	A	A	FURRED WALL AT EXT. WALL	10'-0"	1				113						
114	OFFICE	2	5		A	A	A	A	FURRED WALL AT EXT. WALL	10'-0"	1				114						
115	STAIRWAY	1	5		A	A	A	A		10'-0"	1				115						
116	ELEVATOR	4	4	NO COVE BASE	F	F	F	F		-	5				116						
117	CONFERENCE	2	5		A	A	A	A		10'-0"	1				117						
118	GENERAL OFFICE	1	5		A	A	A	A		-	3				118						
119	BREAK ROOM	1	5		A	A	A	A		10'-0"	1				119						
120	EQUIPMENT	1	5		C	C	C	C		9'-0"	2				120						
121	SERVER / SITE ROOM	8	5		A	D	A	A		9'-0"	2				121						
122	(E) JANITOR	7	-		E	E	E	E		-	4				122						
123	(E) OFFICE	7	-		E	E	E	E		-	4				123						
124	OFFICE	7	-		E	E	E	E		-	4				124						
125	INTERVIEW	7	5		A	A	E	E		9'-0"	1				125						
126	CUBE	7	4		E	-	A	E		-	4				126						
127	(E) OFFICE	7	-		E	E	E	E		-	4				127						
128	(E) ENTRY	7	-		E	E	E	E		-	4				128						
129	(E) OFFICE	7	-		E	E	E	E		-	4				129						
130	CUBES	7	5		E	E	E	-		-	4				130						
131	(E) CONFERENCE	7	-		E	E	E	E		-	4				131						
132	(E) WORK	7	-		E	E	E	E		-	4				132						
133	(E) BREAK ROOM	7	-		E	E	E	E		-	4				133						
134	(E) LACT	7	-		E	E	E	E		-	4				134						
135	(E) HALLWAY	7	-		E	E	E	E		-	4				135						
136	(E) WOMEN'S RESTROOM	7	-		E	E	E	E		-	4				136						
137	(E) MEN'S RESTROOM	7	-		E	E	E	E		-	4				137						
138	WAREHOUSE	1	-		E	E	C	C		-	4				138						
139	I.T. STORAGE	1	-		C	C	C	C		10'-0"	2				139						
	(SEE SHEET A4.2 FOR CONT.)																				

17

FINISH SCHEDULE - GROUND FLOOR

PROPOSED TENANT IMPROVEMENT FOR:

CENTER FOR HUMAN SERVICES

2000 W. BRIGGSMORE, SUITE 1
MODESTO, CALIFORNIA 95350

REVISIONS:

DRAWN: H. HADARI

DATE: 07/28/2014

FILE: 216-A41

JOB: 61.216

PRINT DATE:

FINISH SCHEDULE
GROUND FLOOR

A4.1

L Street Architects

L i m i t e d

1404 L Street
Modesto, California 95354
209-575-4415 209-575-4374 fax
www.lstreetarchitects.com

ARCHITECTS • LICENSED ARCHITECTS
ROBERT T. DOUGLASS
C-8827
RENEWAL 11/29/15
STATE OF CALIFORNIA