

BELENA BOREHOLE SERVICES

DRILLING CONTRACTORS AND WATER ENGINEERS

BISSIL TOWN KAJIADO

P.O BOX 674 KAJIADO +254729959001


RE CHURCH OF CHRIST LEBOO WATER WELL -KUMPA LOCATION-KAJIADO DISTRICT.

THANK YOU FOR YOUR REQUEST, THE COST WILL BE AS DETAILED BELOW:

Items	Description	Qty	Unit	Rate	Amount
1.	Mobilization and demobilization of drilling equipment, including transportation of tools supplies and personal				20,000
2.	Erecting and dismantling include setting up camp and supplying water for drilling and camp use				10,000
3.	Drilling 200mm borehole	200	M	4,000	800,000
4.	Supply and install 150mm diameter, plain casing	200	M	1,000	200,000
5.	Supply and install 150mm diameter slotted PVC casing	60	M	2,500	150,000
6.	Grouting to ensure a sanitary seal at surface end including construction casing anchor slab				10,000
7.	Fencing the site, the gate and fixing the sign post				15,000
8.	Test pumping				30,000
9.	Chemical analysis				5,000
10.	Supply and install 10KVA generator			200,000	200,000
11.	Supply and install 10,000liters tank			70,000	70,000
12.	Supply and install PVC pipes approximately 300m			20,000	20,000
13.	Supply and install a submersible pump complete with control panel, low level control, thermal protection and power surge protection to include draw PPR pipes, borehole cap and air line				92,000
14.	Plumping work, G1 fitting and cementation				
15.	Cattle trough (one)			10,000	10,000
16.	Pump house (sketch attached)				163,000
	TOTAL				1,800,000

YOURS FAITHFULLY

RICHARD G.KIHUHA



BELENA BOREHOLE SERVICES


DRILLING CONTRACTORS AND WATER ENGINEERS

BISSIL TOWN KAJIADO

P.O BOX 674 KAJIADO +254729959001

PUMP HOUSE

OPTION ONE



This is strongly built single room approximately 3mx3m and standard height .the room is ventilated to allow engine cooling .the roof is steel reinforced concrete for security and single strong steel door fitted

Cost as follows :

Quarry bricks	kshs 50,000
Cement	ksh 20,000
Steel bars	ksh 20,000
Steel door	ksh 8,000
Finishing	ksh 15,000
Labour	ksh 40,000
Timber	kshs 10,000
Total	ksh 163,000

Yours faithfully

RICHARD G. KIHUHA