1 PRESENTATION PLAN - LOWER LEVEL
1/8" = 1'-0"

2 PRESENTATION PLAN - UPPER LEVEL
1/8" = 1'-0"

SHEET NOTES

CONSTRUCTION PLAN NOTES:

1. ALL GRAY WALLS EXISTING TO REMAIN.
2. AREAS INDICATED IN GREY ARE NOT IN SCOPE
3. ALL A3 WALLS TO BE 3 1/2" WOOD STUDS WITH 1 LAYER OF 5/8" GWB ON BOTH SIDES.
4. ALL A5 WALLS TO BE 5 1/2" WOOD STUDS WITH 1 LAYER OF GWB ON BOTH SIDES.
5. ALL A5A WALLS TO BE 5 1/2" WOOD STUDS WITH 1 LAYER OF TYPE X GWB ON BOTH SIDES WITH A 1 HR RATING.
6. ALL DIMENSIONS TO FACE OF STUDS.
7. SCOPE OF WORK IN EXISTING TOILET ROOMS LIMITED TO NEW FINISHES, SEE FINISH PLAN FOR MORE INFORMATION.
8. NEW ELEVATOR TO BE LIMITED USE/LIMITED APPLICATION (LU/LA) ELEVATOR TYPE 1 L 48" X 54" WITH 2 STOPS AND A 9'-4" FLOOR TO FLOOR DIMENSION.
9. EXISTING KITCHEN EQUIPMENT TO BE STORED AND REUSED IN NEW KITCHEN, RELOCATE EXHAUST HOOD AND ALL SERVICE CONECTIONS.
10. ALL NEW STAIRS TO HAVE MAAB COMPLIANT HANDRAILS.

GENERAL NOTES

TYPICAL CONSTRUCTION NOTES:

TYPICAL SLOPED ROOF CONSTRUCTION:
ASPHALT SHINGLES
CONTINUOUS ICE AND WATER SHIELD
5/8" PRESSURE TREATED PLYWOOD SHEATHING
WOOD TRUSS
12" BATT INSULATION AT BOTTOM CHORD (R=38)
VAPOR BARRIER
FINISHED CEILING

PARISH HALL ROOF CONSTRUCTION:
ASPHALT SHINGLES
CONTINUOUS ICE AND WATER SHIELD
5/8" PRESSURE TREATED PLYWOOD SHEATHING
2X10 WOOD RAFTERS WITH 6 1/2" SPRAY FOAM INSULATION (R=39)
LVL SCISSOR TRUSSES AT 13'-0" O.C., TRIMMED OUT AND PAINTED
2X6 WOOD FURRING WITH BLOCKING AT 4'-0" O.C.
3/4" PLYWOOD
FINISHED CEILING PANELS

TYPICAL EXTERIOR WALL CONSTRUCTION:
CEMENTITIOUS HARDIE PLANK CLAPBOARDS
1" RIGID INSULATION
1/2" PLYWOOD SHEATHING
2X6 STUD WALL WITH BATT INSULATION (R=21)
CONTINUOUS VAPOR BARRIER
5/8" GWB (2X6 BLOCKING AT ALL HORIZONTAL GWB JOINTS)

TYPICAL FLOOR CONSTRUCTION:
3/4" FINISHED WOOD FLOORING
3/4" PLYWOOD SUBFLOOR
2X12 WOOD JOISTS FLUSH FRAMED WITH BEAMS AT THIRD PIONTS
BEAMS OVER CHAPEL AREA TO BE STEEL, TRANSFER OVER DOORWAYS
BEAMS TO POST DOWN AT INTERIOR WALLS TO FOOTINGS
3/4" FURRING
5/8" GWB CEILING

TYPICAL SLAB CONSTRUCTION:
FINISHED FLOOR
4" CONCRETE SLAB
CONTINUOUS VAPOR BARRIER
CONTINUOUS 2" RIGID INSULATION (R=10)
6" CRUSHED STONE
FILL

TYPICAL FOUNDATION WALL CONSTRUCTION:
10" CONCRETE WALL ON CONCRETE FOOTING; SEE FOUNDATION PLAN FOR SHELVES

Revisions

Issue	Date & Issue Description	Check	By
	Permit Set	March 1, 2016	

© Siemasko + Verbridge, Inc.

Project Name
Renovation/Expansion
Description
SD01 PRESENTATION PLANS
Scale: 1/8" = 1'-0"
Date: March 1, 2016
Drawn by: Author
File Name:
Plot Date: 2/19/2016 12:07:44 PM
Checked by: Checker
Project #:

Proposed New Construction
First Church in Wenham
1 Arbor St
Wenham, MA 01984

Siemasko + Verbridge
126 Dodge Street
Beverly, Massachusetts 01915
www.svdesign.com
Architecture
Interior Design
Landscape Design
Decorating
t 978.927.3355 f 978.927.6365

SD01 PRESENATION PLANS

SD 01

P:\Institutional, Current\First Church in Wenham\07 - CDs\Revit\Local\First Church in Wenham_20160119_CD_stefano.rvt