
Stormwater Treatment System Project Terminal 18 Port of Seattle





400+ Catch Basins

200+ Manholes

19 Miles of Pipe

19 Outfalls

Off-site contribution

Sample Monitoring Results

											Exceedance
Outfall M09	Bench	Q1-15	Q2-15	Q3-15	Q4-15	Q1-16	Q2-16	Q3-16	Q4-16	Average	Frequency
Turbidity	25 NTU	20.9	34	23.1	24.6	12	10.1	27.4	29	22.6	2/8
Zinc	117 ug/L	463.3	300	500	178	190	360	217	289	312	8/8
Copper	14 ug/L	11.6	23	35.1	25.6	10	10	21.9	15.5	19	5/8
ТРН	10 mg/L	0.42	1	2.2	1.4	0.65	0.51	0.707	0.423	0.9	0/8
TSS	30 mg/L	12.2	35.3	25.4	25.2	28.4	10.9	25.8	62.2	28.2	2/8

Phased Implementation Over Five Years

Phase One – End of Pipe treatment for at least 67 acres. Add two OWS at MNR. Complete by October 30, 2016

Phase Two - End of Pipe treatment for a total of at least 124 acres. Complete by October 30, 2018

Phase Three – Complete remainder of site, less any sub-basin qualifying for "off- ramp" with End of Pipe treatment. Complete by October 30, 2020

Phase One Treatment

87.2 Total Acres

Basin 19 / Expansion Area (Matson yard). 56.9 acres.


Basin 3 / CEM and Roadability 13.5 acres. Includes OWS.



Basin 20. Combines with Basin 19 due to proximatey of outfall. 10.3 acres.

Basin 15 / MNR. 4.2 acres. Includes OWS. Basin 14 / MNR. 2.3 acres. Includes OWS.

Basic System Components



Modular Wetland

Basin 14



Chitosan Enhanced Sand Filtration System Basin 19/20









Basin 19 Flow Splitter



Results

Chitosan Enhanced Sand Filtration System


11/14/2016	Turbidity	Ph	Zinc	Copper	TSS
Bench	25 NTU	5.0-9.0 su	117 ug/L	14 ug/L	30 mg/L
M19 Raw	20.6	7.23	279	72.6	43.7
M19 Treated	0.31	6.93	40.9	5.46	0
% Reduction	98		85	92	100


Modular Wetland systems

11/15/2016	Turbidity	Ph	Zinc	Copper	TSS
Bench	25 NTU	5.0-9.0 su	117 ug/L	14 ug/L	30 mg/L
Raw Average	24.8	7.3	298	17.7	52.7
M15	8.44	7.6	76.4	1.87	0
% Reduction	66		74	89	100

Infrastructure Issues







07-08-15. Outfall pipe in Basin 19. Video inspection reveals break in pipe approximately 40 feet from the manhole. Pipe has settled and the joints along it's length are openning. Ground water infiltrates all along pipe. Tidal influx is substantial. There are likely significant voids above and below the break.



Questions?