

ENGINEER'S ESTIMATE OF PROBABLE CONSTRUCTION COST  
WEST TRAIL REPAIRS - SHORELINE PROTECTION ALTERNATIVE #1

Client: San Mateo Harbor District  
Project: Pillar Point Harbor - West Trail Repairs

Date: 04-12-12

Description	Quantity		Cost		Total Material Cost	Total Labor Cost	Total Unit Cost	Total Cost
	No	Unit	Mat'l	Labor				
<b>General Description of Work</b>								
Provide protection against further shoreline erosion by placing stone rip rap along approximately 300 feet on shoreline. Alternatives to rip consist of a soldier pile wall with timber or concrete lagging, steel sheet pile bulkhead, cast-in-place concrete retaining wall or shotcrete and soil nail wall. Repairs are required to two drainage culverts. Vegetation at southern trail portion for erosion protection and repair and stabilization for erosion occurring on hillside								
Mobilization	1	LS		\$30,000.00		\$30,000.00	\$30,000.00	\$30,000.00
<b>Northern Portion of Path - Erosion Protection</b>								
Alternative #1 - Riprap	420	CY	\$87.00	\$65.00	\$36,540.00	\$27,300.00	\$152.00	\$63,840.00
<b>Repairs at Stacked Culverts</b>								
Installation of underground junction structure, and connection of existing 24" pipe to this structure. Assume demo of existing culverts, and installation of new 24" culvert under path								
	1	LS	\$2,500.00	\$6,900.00	\$2,500.00	\$6,900.00	\$9,400.00	\$9,400.00
<b>Removal of Concrete Rubble</b>								
	1	LS	\$0	\$10,000.00	\$0	\$10,000.00	\$10,000.00	\$10,000.00
<b>Southern Portion of Path - Erosion Protection</b>								
Place soil and vegetate	200	SF	\$0.06	\$2.75	\$12.00	\$550.00	\$2.81	\$562.00
Vegetation of desire paths	150	SF	\$0.06	\$2.75	\$9.00	\$412.50	\$2.81	\$422.00
<b>Hillside above Path - Erosion Protection</b>								
Vegetate Hillside	20,000	SF	\$0.06	\$1.35	\$1,200.00	\$27,000.00	\$1.41	\$28,200.00
Temporary Fencing	600	LF	\$5.75	\$9.00	\$3,450.00	\$5,400.00	\$14.75	\$8,850.00
Materials Subtotal					\$43,711.00			
Subtotal Labor + Materials								\$151,274.00
Hard Costs Estimating Contingency 5%								\$7,564.00
Subtotal Hard Costs								\$158,837.00
Sales Tax on Materials 8.50%								\$3,715.00
General Conditions 10%								\$15,884.00
Bond & Insurance 3%								\$5,518.65
Subtotal								\$25,118.00
General Contractor's Fee (OH&P) 8%								\$14,716.40
Overall Estimating Contingency 20%								\$37,894.73
<b>TOTAL ESTIMATED CONSTRUCTION COSTS (with ALT #1 Shoreline Repair)</b>								<b>\$236,566.00</b>



