			HIGH RISK	
	CATEGORY OF WORK	HAZARDS & RISKS	RISK CONTROL MEASURES IMPLEMENTATION OF CONTROLS	PERSONS RESPONSIBLE
1	Working at heights & Fallin WHS Regulation 315 (NSW) / Work task – see subsections			
<i>1A</i>	Working on a roof	Roof edge Sloped roofs Working above dangerous machinery or equipment. Risk - Worker falls off the roof resulting in serious injury or death.	 Install edge protection (e.g., guardrails, scaffolding) in compliance with AS/NZS 4994: Temporary Edge Protection. Harness systems must be used where guardrails are not practical. Conduct a pre-start inspection, verifying: a. Stability of edge protection. b. Proper fitting and functionality of harness systems. c. Access points and fall zones are clear of hazards. Use of a fall arrest system (e.g., safety harness) when working at heights if there is a risk of falling that cannot be eliminated or minimized using higher-level controls. Inspect the roof surface for stability and ensure it is free from hazards like loose tiles, slippery surfaces, or fragile materials prior to commencing work. Avoid roof work in wet, windy, or extreme heat conditions. Use roof ladders or walk boards for added stability on sloped or fragile roofs. Ensure workers are familiar with the emergency rescue plan. Display warning signs and restrict unauthorized access to the work zone. Adhere to all warning signs and restricted area notices within the work zone. Duse tool lanyards to prevent tools from falling off the roof. All materials and tools must be secured to prevent falls in compliance with WHS Ensure edge protection installation is conducted by a competent person and inspected before use. Equip workers with a fall arrest syste (e.g., safety harness) that complies with AS/NZS 1891: Industrial Fall-Arrest Systems and Devices. Anchor points must be: o Installed according to the manufacturer's specifications. Assign a site supervisor to oversee roof work, ensuring compliance with control measures. Conduct periodic audits during roof works. Ensure adherence to all warning signs and restricted area notices within the work zone. Provide workers with Working at Heights training certified to RIIWHS204E: Work Safely at Heights training certified to RIIWHS204E: Work Safely at Heigh	Carpenters

1B	Working from scaffolding All scaffolding used on-site must be erected, inspected, and maintained in accordance with AS/NZS 4576: Scaffolding Guidelines and AS/NZS 1576: Scaffolding Design & Construction, ensuring compliance with fall protection measures.	Hazard – • Scaffold collapse • Slips or falls from scaffold Risk - Worker falls from scaffold resulting in serious injury or death.	Regulation 315 (NSW) / OHS Regulation 44 (VIC). 12. Workers must not work directly below elevated work areas unless exclusion zones are in place. 1. Erect scaffolding according to AS/NZS 4576: Guidelines for Scaffolding. 2. Ensure scaffolding is inspected:	
1C	Working from ladders on ceilings above 2 metres	 Hazard – Ladder tipping Standing on top rung of ladder (continues) Slips from ladder Risk - Worker falls from the ladder, resulting in serious injury or death. 	 Use ladders that comply with AS/NZS 1892: Portable Ladders standards. Ensure ladders are: a. The appropriate height for the task (avoid overreaching). b. Rated for the intended load capacity. Place ladders on a flat, stable, and nonslip surface. Secure ladders at the top or bottom to prevent movement. Maintain a 4:1 ratio between the height of the ladder and its base distance from the wall. Always maintain three points of contact (two feet and one hand or two hands and one foot). Conduct pre-use inspections for: Structural integrity (e.g., no cracks, bends, or missing components). Stable and clean rungs to avoid slips. Provide workers with ladder safety training, including: Proper ladder setup. Emergency procedures in case of a fall. Ensure a site supervisor monitors compliance with ladder safety procedures. Conduct pre-use inspections for: Structural integrity (e.g., no cracks, bends, or missing components). Stable and clean rungs to avoid slips. Provide workers with ladder safety training, including: Proper ladder setup. Emergency procedures in case of a fall. Ensure a site supervisor monitors compliance with ladder safety procedures. Conduct periodic safety checks during ladder work. 	Site Supervisor Safety Officer Workers

			8. 9. 10. 11.	ladder. Avoid overreaching; reposition the ladder as necessary. For work exceeding 2 meters, use a fall arrest system (harness) where possible. Anchor points for the fall arrest system must comply with AS/NZS 1891: Industrial Fall-Arrest Systems and Devices. Use tool belts or pouches to carry tools to keep hands free. All materials and tools must be secured to prevent falls in compliance with WHS Regulation 315 (NSW) / OHS Regulation 44 (VIC). Workers must not work directly below elevated work areas unless exclusion zones are in place.			
2	Welding Work tasks - Welding tasks, including arc welding, gas welding, or oxy-acetylene cutting.	 Fire and Explosion. Exposure to toxic fumes from metals, coatings, and welding rods. Radiation Electric Shock Ergonomic Strains Risk – Fatal injuries High temperatures and sparks can ignite flammable materials. Ultraviolet (UV) and infrared (IR) radiation exposure causing burns or eye damage (arc eye). Improper grounding or contact with live parts of the equipment. Awkward postures or repetitive motions causing musculoskeletal issues. Potential for severe burns, 	 3. 4. 5. 6. 7. 	Install welding screens to protect nearby workers from UV radiation. Use local exhaust ventilation or portable fume extractors to minimize exposure to toxic fumes. Ensure proper grounding of welding equipment to prevent electrical hazards. Use fire-resistant blankets or barriers to contain sparks and heat. Use PPE a. Welding Helmet. b. Flame-Resistant Clothing c. Heavy-duty, flame-resistant welding gloves. d. Respiratory Protection - Use P2 or P3 respirators when ventilation is insufficient. e. Steel-toe, heat-resistant boots. Store flammable materials away from welding zones as per AS 1674.1: Safety in Welding and Allied Processes. (continues) Ensure welding equipment complies with AS/NZS 60974: Arc Welding Equipment.	•	Conduct pre-task safety checks, including equipment inspection. Install and maintain engineering controls (e.g., ventilation and fire protection). Provide task specific training to workers on safe welding practices and emergency procedures. Enforce the use of PPE during welding activities. Conduct pre-task inspections of welding equipment and PPE. Perform regular audits and inspections to ensure controls remain effective.	Site Supervisor Carpenters Welders Safety Officer

		respiratory damage, long- term health effects, or fatal injuries due to electric shock or explosion.	8. 9.	Use UV radiation protective barriers for nearby workers. Implement localized fume extraction systems where natural ventilation is insufficient.			
3	Movement of a powered mobile plant Type of work - Work carried out in an area at a workplace in which there is any movement of powered mobile plant	Hazard - Workers struck by moving plant or machinery. Risk- Worker injury (moderate to severe) or death.	7.	All forklifts, telehandlers, and other powered industrial trucks must comply with AS 2359.2: Powered Industrial Trucks – Safe Use. Pedestrian exclusion zones must be maintained around all powered mobile plant, per WHS Regulation 215 (NSW) / OHS Regulation 98 (VIC). a. Exclusion zones must be maintained at a minimum of 2 meters from pedestrians, as per AS 2359.2. Operators must hold a valid high-risk work license where required, in accordance with WHS Regulation 96 (NSW) / OHS Regulation 44 (VIC). Ensure reversing alarms and flashing beacons are functional as per Regulation 215 (WHS Regs 2011) Daily pre-start safety checks must be completed on powered industrial trucks, in compliance with AS 2359.2 and site-specific traffic management plans. a. Faulty brakes, steering, or hydraulics. b. Non-functional lights, alarms, or beacons. c. Leaks or structural defects. d. Test alarms and emergency stop controls daily. Restrict the use of mobile plant during adverse weather conditions (e.g., heavy rain, strong winds). Ensure ground surfaces are stable and free from hazards like mud or loose gravel. Ensure plant is parked on level ground during loading or unloading.	•	Establish and enforce exclusion zones around mobile plant to separate pedestrians from operating areas. Use: Physical barriers (e.g., fencing or cones). Clear signage indicating restricted access. Schedule regular maintenance of all plant is undertaken to reduce mechanical failures. Conduct regular toolbox talks to reinforce safe practices for mobile plant operations. Train workers on: Identifying and avoiding mobile plant hazards. Procedures for reporting unsafe plant conditions or behaviors. Develop & enforce site specific traffic management plans to include: Exclusion zones for pedestrians (2m minimum clearance). Competency verification for plant operators. Spotters required for reversing vehicles.	Plant Operators Safety Officer Site Supervisor

			9. Use wheel chocks or stabilizers where necessary to prevent movement.	
4	Work near pressurised gas pipes or mains Work task - Excavation above gas lines	 Hazard – Puncturing or damaging a gas line during excavation. Release of gas causing fire, explosion, or asphyxiation. Risk - Serious injuries, fatalities, or significant damage to infrastructure. 	 Do not commence work if you have not been provided with the locations of underground utilities. Clearly mark the location of gas pipes onsite using color-coded spray paint or flags. Use hand tools for excavation within 1 meter of gas lines to minimize damage risk. Avoid the use of heavy machinery directly above marked gas lines. Keep workers at a safe distance during excavation. Ensure location of gas lines are known by contacting Dial Before You Dig (DBYD) to locate and map underground utilities before work begins. Communicate findings with all workers. Include gas line locations in toolbox talks and site plans. Ensure workers are trained in gas safety protocols and understand the risks of gas exposure. Assign a competent supervisor to oversee excavation activities. 	Site Supervisor Machine Operators Safety Officer
5	Work involving tilt-up or precast concrete. Work task - Erecting tilt-up or precast concrete panels on-site.	Hazard - Panel becomes unstable during erection and collapses. Risk - Workers in the fall shadow are struck by the collapsing panel and are seriously injured or killed.	 Install braces in accordance with AS 3850: Prefabricated Concrete Elements. Conduct a structural engineer's inspection and approval before removing bracing. Exclude workers from the fall shadow zone during lifting operations. Erect bracing systems under supervision of a competent person. Inspect bracing systems daily and after extreme weather events.	Site Supervisor Crane Operators
6	Area with traffic Work Task - Work carried out on, in or adjacent to a road or other traffic corridor that is in use by traffic other than pedestrians.	Hazard - Public vehicles; Interaction with live traffic. Risk — 3. Vehicles entering the work area unexpectedly or inadequate traffic management leading to collisions. 4. Worker struck by vehicle causing injury or death.	 Develop and implement a traffic management plan. Establish exclusion zones using physical barriers (e.g., fencing, barricades, or cones). Install clear signage to indicate restricted access and direct traffic flow. Deploy trained traffic controllers to manage pedestrian and vehicle movement. Reduce speed limits near the work zone and ensure compliance. Conduct daily inspections to verify traffic control setups remain effective. Traffic Management Plan: Site Supervisor to oversee the creation and execution of the plan, ensuring compliance with local regulations. Barriers and Signage: Workers to install physical barriers and signage before starting work and verify they are clearly visible and functional. Traffic Controllers: Trained personnel to actively manage vehicle and pedestrian movement and enforce exclusion zones. Inspections: Safety Officer to conduct routine checks of the traffic control 	Site Supervisor. Traffic Controllers. Safety Officer.

7	Load-bearing structure demolition Work task - Removing bracing from a wall using an excavator	Hazard – 1. Unsupported building materials. 2. Flying debris. Risk – 1. Wall collapses on worker or others 2. Flying debris hits worker	 Fit an open cab excavator with a protective structure to minimise the risk of being struck by a falling object. Ensure all workers wear appropriate PPE, including hard hats, safety glasses, steel-toe boots, and high-visibility clothing. Follow the pre developed detailed demolition plan, including sequencing to prevent structural instability. Restrict access to the demolition zone using barriers and signage. Conduct a pre-demolition inspection to 	 measures, addressing any deficiencies immediately. Workers to use PPE consistently and correctly throughout the demolition process. Site Supervisor to oversee the creation and execution of the demolition plan, ensuring that the sequence minimizes risks. Establish and maintain exclusion zones around the demolition area, with clear signage and barriers to prevent unauthorized entry. Conduct a structural assessment of 	Site Supervisor. Safety Officer. Machine Operators.
0	Disturbing Ashastos	Hazard –	identify and address potential hazards. Only licensed aspestos removalists may	building before demolition and a visual check after each step to identify any unexpected risks. The person removing the asbestos has	Safety Officer
8	Work task – Demolition or renovation of a wall containing asbestos sheeting. Any asbestos removal must comply with the How to Safely Remove Asbestos – SafeWork NSW & WorkSafe VIC Code of Practice.	 Hazard – Releasing asbestos fibers into the air during handling, demolition, or renovation. Inhalation of fibers causing asbestosis, mesothelioma, or lung cancer. Risk - High risk of long-term health effects due to airborne asbestos exposure such as asbestosis or mesothelioma. 	Only licensed asbestos removalists may remove more than 10m² of non-friable asbestos. This is defined as 10 square meters of non-friable asbestos (also known as bonded asbestos) in total. Non-friable asbestos refers to asbestos-containing material (ACM) that is solid and unlikely to release fibers unless disturbed, such as cement sheeting. The below measures are for Mckeone employees & subcontractors who are not licensed to carry out Asbestos removal. The following safety measures MUST always be adhered to, no exceptions: 1. Workers must wear provided disposable Type 5 coveralls, nitrile gloves, and P2 or P3 respirators certified under AS/NZS 1716. 2. Employ wet methods (lightly spray the material with water containing detergent) to minimize dust and fiber release. Containment: 1. Ensure the work area is sealed or restricted to prevent the spread of asbestos fibres	 The person removing the asbestos has completed asbestos awareness training or equivalent. Post warning signs to restrict access to asbestos-affected areas. Prior to all work on a site where asbestos may be present: The asbestos register is checked to confirm the presence, type, and location of asbestos. If no register exists (e.g., in older homes), a licensed asbestos assessor is engaged to inspect the site and identify asbestos-containing materials. If asbestos is found, a site-specific SWMS will be developed in accordance with the levels & handling required to remove the asbestos. Ensure asbestos removal is performed by a Class A (friable) or Class B (nonfriable) licensed contractor, as required by WHS regulations. Provide disposable Type 5 coveralls, 	Safety Officer Site Supervisor Workers

			 Use 200-micron plastic sheeting to seal the work area and minimize fibre release. Disposal & Waste Management: Double-wrap all asbestos waste in heavyduty plastic and label it as "Asbestos Waste". Transport waste to a licensed asbestos disposal facility. Prohibited Activities: Do not use power tools, abrasive cutting tools, or high-pressure water to remove or clean asbestos materials. 	nitrile gloves, and P2 or P3 respirators certified under AS/NZS 1716. Provide asbestos awareness training to all workers involved in the task. Ensure workers understand the specific asbestos risks on the site. Conduct air monitoring to ensure fiber concentrations remain below the permissible exposure limits. A clearance certificate must be obtained before reoccupying the site.	
9	Confined Space Work Work task – Performing tasks inside confined spaces where oxygen levels or hazardous gases could be an issue. Confined spaces can include but are not limited to: • Sewers & stormwater drains • Crawl spaces under houses • Storage tanks, pits, sumps, or vats • Manholes and deep trenches (over 1.5m with limited exit) • Tunnels, ducts, and pipelines • Void spaces within walls, ceilings, or under floors All confined space work must comply with AS/NZS 2865: Confined Spaces, including obtaining a confined space entry permit and using continuous atmospheric monitoring, as	 Hazard – 3. Oxygen deficiency. 4. Toxic atmospheres. 5. Engulfment by liquids or materials. Risk – Suffocation, poisoning, or serious injury due to lack of oxygen or exposure to hazardous gases. 	 Ensure a confined space entry permit has been obtained. Use continuous atmospheric monitoring, as per WHS Regulation 67 (NSW) / OHS Regulation 56 (VIC). Familiarize yourself with emergency rescue plans before entry. Conduct atmospheric testing before entry. Continuous gas monitoring must be used in confined spaces. Implement a confined space entry permit system. Ensure proper ventilation and atmospheric monitoring. Provide workers with appropriate PPE (e.g., respirators). Train workers in confined space entry and emergency rescue procedures. Ensure a competent standby person is present during all confined space work. 	 Site Supervisor to ensure all confined space entry permits are completed. Emergency rescue plans must be established before entry. Safety Officer to confirm atmospheric testing results before work begins. Workers to wear and correctly use all required PPE. Conduct regular training and emergency drills for confined space rescue. 	Site Supervisor. Safety Officer. Workers.

	per WHS Regulation 67 (NSW) / OHS Regulation 56 (VIC				
10	Crane Operations and Lifting Work Task - Operating cranes or other lifting equipment to move heavy loads such as prefabricated panels, or machinery.	 Hazard – Load swings or drops. Crane overturning or structural failure. Ground instability. Risk - Injury or death from falling loads or equipment failure. 	 Use licensed and certified crane operators. Conduct pre-lift inspections and develop lift plans. Establish exclusion zones around crane operations. Use taglines to guide loads and reduce swing. Inspect crane stability and ground conditions before operation. 	 Crane operators to follow lift plans and perform daily equipment checks. Site Supervisor to monitor exclusion zones and ensure barriers/signage are in place. Safety Officer to conduct periodic audits of crane operations. 	Site Supervisor. Crane Operators. Safety Officer.
11	Hot Work Work Task - Performing welding, grinding, soldering, or other work that may produce heat or sparks	 Hazard – Sparks causing fires or explosions. Exposure to extreme heat and UV radiation. Risk - Burns, eye injuries, or fire damage. 	 Designate hot work zones away from flammable materials. Use fire blankets and barriers to contain sparks. Ensure fire extinguishers and suppression equipment are readily available. Provide workers with welding helmets, flame-resistant clothing, and gloves. 	 Site Supervisor to inspect and approve hot work zones before starting tasks. Workers to wear and maintain appropriate PPE during tasks. Safety Officer to ensure fire suppression equipment is functional and accessible. 	Site Supervisor. Welders. Safety Officer.
			MEDIUM RISK		
	CATEGORY OF WORK	HAZARDS & RISKS	RISK CONTROL MEASURES	IMPLEMENTATION OF CONTROLS	PERSONS RESPONSIBLE
1	Manual Handling Work task - Lifting, carrying, or moving heavy materials, repetitive tasks (e,g. hammering) Loading/unloading equipment or materials from vehicles.	Hazard - Strains, sprains, or musculoskeletal injuries. Risk - Potential for injury from improper lifting techniques or overexertion.	 Apply team lifting for heavy or awkward items. Train workers in proper lifting techniques. Adhere to AS/NZS 1269: Manual Handling Code of Practice. Limit load weights to 20 kg for singleperson lifts. Use trolleys or mechanical aids for heavier materials. 	 Conduct manual handling training every 6 months. Use team lifts for materials exceeding 20 kg. Provide trolleys & mechanical aids. Onsite workers enforce team lifting policies. 	Director's Site Supervisor Safety Officer
2	Use of Power Tools Work task - Operating saws, drills, jackhammers, nail guns, sanders, circular & drop saws.	Hazard - Kickbacks, cuts, punctures, or tool malfunctions. Risk - Potential for serious injury if tools are misused or poorly maintained.	 Use PPE such as gloves, goggles, and ear protection. All portable electrical tools must be tested and tagged every 3 months, per AS/NZS 3760. Use tools equipped with safety guards and 	 Follow the tool inspection schedule. Conduct pre-task toolbox talks. Issue PPE to workers. Tag out and report faulty tools immediately. Assign supervision for apprentices 	Director's Carpenters Site Supervisor Safety Officer

			 auto-shutoff features. 4. Provide task-specific training on tool operation. 5. RCDs must be installed on all circuits supplying portable electrical equipment. 6. Workers must inspect power cords and tools before use and report defects immediately. 	using power tools. • Provide PPE such as gloves, goggles, and ear protection.	
3	Working at Low Heights Work task - Tasks performed on ladders or low scaffolding under 2 meters.	Hazard - Falls, slips, or trips. Risk - Minor to moderate injuries from a fall.	 Use stable ladders and scaffolding on firm ground. Avoid overreaching while on ladders. Inspect ladders and scaffolding for defects before use. 	 Conduct regular equipment inspections. Enforcement proper ladder use guidelines. 	Site Supervisor Safety Officer
4	Use of Chemicals & Adhesives Work task - Applying adhesives, sealants, or paints.	Hazard - Exposure to fumes or skin contact with hazardous substances. Risk - potential for skin irritation or respiratory problems.	 All hazardous chemicals must be labeled under GHS regulations. Chemicals must be labelled & stored in accordance with the SDS. Only trained personnel may handle hazardous substances. Ensure adequate ventilation in work areas. Use low-VOC products when possible. Use provided gloves, goggles, and respirators. 	 Ensure proper storage of chemicals and provide Safety Data Sheets (SDS) for all products. Safety Data Sheets (SDS) must be reviewed every 5 years and available on-site. 	Site Supervisor Carpenters Safety Officer
5	Exposure to Dust & Particulates Work task - Cutting or sanding wood, plaster, or cement boards.	Hazard - Dust inhalation and respiratory issues. Risk- Long-term exposure can lead to conditions like silicosis.	 Use water suppression or dust extraction systems for all cutting or sanding. Use P2 or P3 respirators certified under AS/NZS 1716: Respiratory Protective Devices. Conduct regular air quality monitoring. 	 Provide P2 or P3 respirators certified under AS/NZS 1716: Respiratory Protective Devices. Train workers on the proper use and maintenance of respirators. Ensure dust control equipment is inspected daily. 	Site Supervisor Carpenters Safety Officer
6	Working with Temporary or Unstable Structures Work task - Fixing framework or bracing temporary structures.	Hazard - Collapse of structures or shifting materials. Risk - Risk of injury from falling or collapsing structures.	 Use proper bracing techniques. Inspect temporary structures for stability before use. 	Assign inspections before every shift and train workers on bracing techniques.	Site Supervisor Carpenters
7	Electrical Safety Work task - Using portable electrical tools in damp or dusty environments.	Hazard - Electric shock or short circuits. Risk- Injury from exposure to faulty or unsafe electrical	 Ensure tools are tested and tagged. Use Residual Current Devices (RCDs). 	Implement a test-and-tag schedule and conduct site audits for electrical safety compliance.	Electricians Site Supervisor Carpenters Safety Officer

		equipment					
8	Weather Work task - Working in wet, windy, or hot conditions.	Hazard - Slips, dehydration, or heat stress. Risk - Environmental factors can lead to moderate injuries or health issues.	1. 2.	Reschedule work in extreme weather. Provide hydration stations and sun protection.	•	Monitor weather forecasts and establish shade/rest areas.	Site Supervisor Safety Officer
9	Noise Exposure Work task - Using noisy equipment like saws or nail guns	Hazard - Hearing damage from prolonged exposure. Risk - Cumulative hearing loss over time.	1.	Use hearing protection compliant with AS/NZS 1270: Hearing Protectors. Such as earplugs or earmuffs. Limit noise exposure to no more than 85 dB(A) over an 8-hour shift.	•	Provide hearing protection compliant with AS/NZS 1270: Hearing Protectors. Such as earplugs or earmuffs. Rotate workers between noisy and quieter tasks to reduce exposure. Conduct annual audiometric testing for workers in high-noise areas.	Site Supervisor Safety Officer Project Manager
10	Handling Prefabricated Components Work task - Installing prefabricated panels or trusses.	Hazard - Risk of manual handling injuries or dropping heavy components. Risk - Potential for strains or impact injuries.	1.	Use cranes or lifting equipment for heavy components. Plan and communicate lifting strategies.	•	Schedule lifting tasks with adequate personnel and machinery.	Site Supervisor Project Manager Builders
11	Exposure to Extreme Weather Work Task - Working outdoors in extreme conditions, such as hot, cold, or wet weather.	Hazard – Heat stress, sunburn, dehydration. Hypothermia in cold weather. Slips or falls during rain. Risk – Health conditions as above	1. 2. 3.	Monitor weather forecasts and reschedule work during extreme conditions. Provide hydration stations, shaded rest areas, and appropriate PPE (e.g., sun hats, rain gear). Train workers to recognize signs of heat stress or hypothermia.	•	Site Supervisor to check weather conditions daily and adjust schedules as needed. Safety Officer to ensure hydration stations and shade areas are set up on-site. Workers to wear required PPE and participate in weather safety training.	Site Supervisor. Safety Officer.
12	Traffic Management Work Task - Managing the flow of vehicles and foot traffic around construction zones near public roadways.	 Hazard – Interaction with public vehicles. Workers struck by vehicles in work zones Risk – Severe injury or death from vehicle collisions. 	1. 2. 3.	Develop and implement a traffic management plan. Use barriers, signage, and speed limit enforcement. Deploy trained traffic controllers to manage vehicle flow.	•	Traffic controllers to manage vehicle flow and enforce restricted zones. Site Supervisor to verify traffic control plans are in place and adhered to. Safety Officer to conduct routine inspections of traffic management setups.	Site Supervisor. Traffic Controllers.
				LOW RISK			
	CATEGORY OF WORK	HAZARDS & RISKS		RISK CONTROL MEASURES		IMPLEMENTATION OF CONTROLS	PERSONS RESPONSIBLE
1	Measuring and Marking	Hazard – Minor cuts, scratches, or repetitive motion injuries. Risk – Minor injuries not likely to require medical attention.	1. 2. 3.	Use ergonomic tools to reduce strain. Keep measuring and marking tools in good condition. Ensure adequate lighting in the workspace.	•	Inspect tools before use Take breaks from repetitive tasks to reduce strain.	Carpenters
2	General Cleaning Work task - Sweeping, tidying up debris & organizing	Hazard - Minor slips, trips, cuts, or repetitive strain	1. 2.	When undertaking cleaning activities wear sturdy footwear with good grip. Remove obstacles and debris promptly.	•	Assign daily cleaning tasks and provide suitable tools.	Carpenters

	materials. Ensuring there are no trip hazards before leaving	Risk – Minor injuries from falling debris, sharp objects in debris or overexertion.	3. Use dustpans, brooms, and vacuum systems appropriate for the material.4. Do not handle any swept up piles of debris with your bare hands.		
3	Handling Lightweight Materials	Hazard - Dropping items, minor cuts, or scratches. Risk - Minor injuries with negligible impact.	 Use appropriate hand protection (e.g., lightweight gloves) where necessary. Ensure proper storage of tools and materials. 	Regular toolbox talks to remind workers about safe handling techniques.	Carpenters
4	Painting Small Areas Work task - Painting in confined areas.	 Hazard – 1. Minor spills, skin contact with paint, or mild fumes. 2. Slipping on spilled paint. Risk – Irritation to skin & respiratory system. Minor injury caused by ground level slips. 	 Use non-toxic, low-VOC paints when possible. a) If using solvent-based or high-VOC paint: A respirator with appropriate filters for organic vapors, gloves & safety glasses. Always paint in a well-ventilated area. If appropriate ventilation is not possible the following precautions must be taken; a) Low-VOC paints – A P2 mask b) High-VOC paints – A respirator with appropriate filters for organic vapors. c) When ventilation is low - take short fresh air breaks every hour. 	 Review the paint's SDS to understand its specific risks and recommended precautions. Provide workers with SDS for all paints used and Train workers on spill cleanup procedures. 	Carpenters Site Manager Safety Officer
5	Hand-Sanding or Finishing Surfaces	Hazard - Minor abrasions or dust inhalation. Risk - Minimal impact if controls are followed.	 Use dust masks and safety glasses. Use dust collection systems where possible. 	Ensure workers have access to PPE and are trained on safe sanding techniques.	Carpenters
6	Organizing Tools and Equipment	Hazard - Trips, minor pinches, or tool-related scrapes. Risk - Minimal risk of injury.	 Use labelled storage solutions to avoid clutter. Ensure tools are properly secured and sharp edges are covered. 	Conduct routine inspections of storage areas.	Carpenters
7	Basic Maintenance of Non- Electrical Tools	Hazard - Minor cuts or scratches from tool edges. Risk - Minimal injuries that are easy to manage.	 Wear gloves when sharpening or cleaning tools. Use proper sharpening devices and avoid distractions while using. 	Provide guidance on maintenance techniques and enforce PPE use.	Carpenters
8	Mental Health and Fatigue	Hazard – Stress from long hours or high workloads & Fatigue leading to reduced focus and increased accidents. Risk – Decreased performance and increased risk rates.	 Take regular breaks and enforce reasonable working hours. Rotate workers between high-concentration tasks and low-stress activities. Offer access to mental health resources and support. 	 Site Supervisor to monitor worker schedules and ensure breaks are taken. Safety Officer to provide resources and information on mental health support. Workers to communicate if they feel unwell or fatigued. 	Site Supervisor Safety Officer Project Manager Directors